BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:-Construction of drain and culverts in asphalting to cross roads of GKVK layout in ward No:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift up to 1.5m,excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no138,PWD SR 2014-15)	Cum	220.74	75.60	Rupees seventy five and paise sixty only
2	KSRB 4.1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs. with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,TOM of machinery,curing complete as per specifi-ations.Specification no KBS4.1.4.7(Item no4.3,Page no12,PWD SR 2014-15)	Cum	31.08	4847.04	Rupees four thousand eight hundred forty seven and paise four only
3	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs. with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts. conforming etc as per specification&direction of the engineer incharge of work(pwd sr2014-15,p.no13,sno4.11)	Cum	73.56	6085.28	Rupees fsix thausand sixty five and paise twenty eight only
4	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specificatinns.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr2014-15,p.no17,s.no4.46)	Qnt	69.83	7905.60	Rupees seven thousand nine hundred five and paise sixty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP	
				Rate	Rate in Words
5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,hitresses,buttresses plinth and string course including cost of all materials,labour complete asperspecification. Specification no.KBS 4.6.2(pwd sr2014-15,p.no154/4.31)	Sqm	30.80	292.68	Rupees two hundred ninety two and paise sixty eight only
6	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate)	Sqm	198.00	1245.00	Rupees one thousand two hundred forty five only
7	SRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications MORTH specification NO. 406, No. 154, Item No 20.1 of SR 2014-15	Cum	74.25	1438.56	Rupees one thousand four hundred thirty eight and paise fifty six only
8	KSRRB M500-6: providing and applying primer coat with S.S bitumen emulsion on prepared surface of granular base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications MORTH specification NO. 502, No. 157 Item No 21.6 SR 2014-15	Sqm	495.00	35.21	Rupees thirty five and paise twenty one only
9	KSRRB M500-18: providing and laying Semidense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 508 using 40-60 TPH capacity HMP with mechanical paver grading II (25-30mm) with 5% CRMB -55 grade, No. 160/ Item No. 21.21.6 SR 2014-15	Cum	1[illegible].5	[illegible]71.25	Rupees [illegible] thousand [illegible] hundred seventy [illegible]
10	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	220.74	68.04	Rupees sixty eight and paise four only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer,
Dasarahalli Division,
BBMP, Bangalore

Print Count : 2